



**Mercer Street Friends Food Bank
In conjunction and for
TASK**

**Request for Quotation for Walk-in Refrigerator Box
Brand and Model**

**Location: installation will take place at.
72 ½ Escher St. Trenton NJ 08609**

Advertised Sealed Quote/Bid

Contact Person: Paul Jensen

Position: Associate Ed, Operations

Desired Delivery/Installation date is to be completed prior to: **June 1, 2023***

Ship to: 72 ½ Escher St, Trenton NJ 08609

**Billed to: Mercer Street Friends Food Bank
824 Silvia Street
Ewing, NJ 08628**

***Consideration will be given because of Manufacturers production date
Please attached page(s) with detailed and descriptive specifications on
provided sheets or attach your information in your company's format.**

Item: Walk in Refrigerator

(Specifications listed on attached pages)

Required site visit for all bidders:

Appointment must be made prior to submission of bid for site visit.

Contact Person for site visit: Paul Jensen

Contact No. (609) 697-6159

This site visit must be completed prior to submitting quote/bid.

Due Date of Bid: Monday, April 3, 2023

Bid must be sealed to be accepted and delivered by 1pm Date:

Bid will be officially open on; Wednesday April 5, 2023 at 11:00am

All sealed quote/bids are to be either dropped off and/or mailed to:

Mercer Street Friends Food Bank

c/o James G. Allen

824 Silvia Street

Ewing, NJ 08628

**Mercer Street Friends – Food Bank/TASK
Request for Quotation**

**Product:
15’x15’x8’ walk in refrigerator box**

Description/Options:

- 15’x15’x8’ indoor cooler box. *(no floor if applicable via codes/regulations)*
- 4” thick urethane foam, NSF stucco embossed cam-lock galvanize panels with 10-year warranty. 1 year hardware warranty
- 48” horizontal sliding door 4” thick with diamond plate exterior protection, heavy duty jamb guards and strip curtain
- Heated door frame and threshold
- All Electrical materials, labor, and connections to be run from electrical room to condenser and refrigeration unit to be supplied by contractor.
- 2 ea. 48” LED light fixture with switch at door, thermometer, and heated pressure relief vent
- Labor and material to receive and erect the new walk-in refrigerator box.
- 2 hp outdoor winterized condensing unit 208-230/3 with 5-year Copeland compressor or approved equal warranty and new Russell or approved equal fan blower coil with high efficiency fan motors.
- Refrigeration labor and material to install the new 2 hp outdoor condensing unit including placement on roof and hang a new matching blower coil inside refrigerator.
- Labor for refrigeration/condensate piping must exit the building through a penetration cored in building wall which must be sealed upon completion.

- Labor and installation of sprinkler system (if code requires system)
- 60-day craftsmanship warranty
- Please attach all cut-sheets denoting equipment/product

Quote Sheet

(Please attach the following information)

All Quotes/Bid should be listed and/or attached in the following manner:

Base Pricing for Walk In Box:	\$	
Labor, material, installation:	\$	
Condensing unit:	\$	
Labor, material installation condensing unit:	\$	
Electrical work/needs:	\$	
Permits:	\$	
Fees:	\$	
Sprinkler system:	\$	
List any Customer Discounts	\$	
Grand Total/submission bid price	\$	

**Signed and dated by the company representative/installation manager,
complete with contact information.**

Signature & Title

Date

Contact Information: _____

Additional comments/information sheet(s): (please use/list if needed)

